



I. DESCRIPTION

THE WORK SHALL CONSIST OF INSTALLING A PUMP AROUND WHEN CONSTRUCTION ACTIVITIES TAKE PLACE WITHIN THE STREAM CHANNEL.

II. MATERIAL SPECIFICATIONS

SANDBAGS: SANDBAGS SHALL CONSIST OF MATERIALS WHICH ARE RESISTANT TO ULTRAVIOLET RADIATION, TEARING AND PUNCTURE, AND WOVEN TIGHTLY ENOUGH TO PREVENT LEAKAGE OF FILL MATERIAL (I.e., SAND, FINE GRAVEL ETC.).

III. CONSTRUCTION REQUIREMENTS

1. ALL EROSION AND SEDIMENT CONTROL DEVICES SHALL BE INSTALLED AS THE FIRST ORDER OF WORK.
2. THE HEIGHT OF THE SANDBAGS SHALL BE AS INDICATED IN SECTION A-A. THE SANDBAGS SHALL BE PLACED ON A SMOOTH PREPARED SURFACE.
3. ALL EXCAVATED MATERIALS SHALL BE DISPOSED OFF OUTSIDE THE 100 YEAR FLOOD PLAIN UNLESS APPROVED ON THE PLANS BY THE WRA.
4. ALL DEWATERING OF THE CONSTRUCTION AREA SHALL BE PUMPED TO A WRA APPROVED DEVICE.
5. THE PUMP SHALL BE OF SUFFICIENT SIZE TO CONVEY NORMAL STREAM FLOW.
6. SEDIMENT CONTROL DEVICES ARE TO REMAIN IN PLACE UNTIL ALL DISTURBED AREAS ARE STABILIZED AND THE INSPECTING AUTHORITY APPROVES THEIR REMOVAL.

WASHINGTON
SUBURBAN
SANITARY
COMMISSION

APPROVED: 7-26-21

M. J. Hammer
Chief Engineer

STANDARD DETAIL
STREAM PUMP AROUND

SC
10.0