

NOTES:

- DO NOT SET TEST STATION IN ROADWAY. PLACE TEST BOX IN NON-PAVED AREA NEXT TO ROADWAY.
- MAINTAIN SUFFICIENT SLACK IN THE TEST WIRES SO THAT THE WIRES CAN EXTEND A MINIMUM OF 18 INCHES FROM THE TEST BOX.
- 3. TERMINATE WIRES IN TEST BOX WITH RING TERMINALS, SEE STD. DETAIL C/4.0 FOR TERMINAL BOARD CONFIGURATION.
- 4. INSTALL 0.01 OHM SHUNT BETWEEN TERMINALS #1 AND #4.
- RUN ALL WIRES IN 2" PVC SCH. 40 CONDUIT FROM CONNECTION POINT UNTIL THEY REACH THE BOTTOM OF TEST STATION ASSEMBLY
- ROUTE LEAD WIRES E AND F IN 1" SCH 40 PVC CONDUIT.
 TERMINATE CONDUIT AT HORIZONTAL TO VERTICAL TRANSITION
 WHERE LEADS E AND F JOIN OTHER LEADS TO BE BROUGHT
 INTO TEST STATION ASSEMBLY.

WIRING SCHEDULE					
DESCRIPTION	WIRE	TEST STATION TERMINAL	AWG WIRE SIZE	TYPE OF INSULATION	COLOR OF INSULATION
PIPE	A B	1 3	#8 #10	THWN THWN	BLUE BLUE
PERMANENT REFERENCE ELECTRODE	С	6	PER MANUFACTURER	PER MANUFACTURER	PER MANUFACTURES
ANODE HEADER CABLE	D1 D2	4 7	#8 #8	HMWPE HMWPE	BLACK BLACK
PIPE	E F	2 5	#10 #8	THWN THWN	WHITE WHITE

7. PREPACKAGED ANODES

FOR DIP AND STEEL WATER MAINS

PREPACKAGED MAGNESIUM ANODE (TYPICAL), NUMBER AND SIZE AS REQUIRED IN SPECIFICATIONS AND CONTRACT DOCUMENTS.

FOR CONNECTION NEAR EXIST. PCCP WATER MAINS

PREPACKAGED ZINC ANODE (TYPICAL), NUMBER AND SIZE AS REQUIRED IN SPECIFICATIONS AND CONTRACT DOCUMENTS.

WASHINGTON SUBURBAN SANITARY COMMISSION APPROVED: 7-26-21

Milk Harrican

Chief Engineer

STANDARD DETAIL

SACRIFICIAL ANODE INSTALLATION AND TEST STATION PLACEMENT 2.2