

NOTES:

- 1. PRECAST CONCRETE f'c=5000 PSI . 28 DAYS.
- 2. REINFORCEMENT SHALL CONFORM TO ASTM C-478.
- 3. CAST LIFT LUGS ARE REQUIRED FOR 4" AND 6" RINGS.

WASHINGTON SUBURBAN SANITARY COMMISSION APPROVED: 2-1-21

My Harrie

Chief Engineer

STANDARD DETAIL

24-INCH PRECAST CONCRETE MANHOLE TRANSITION RING

S 4.21