

NOTES:

- 1. SEE DETAIL C/1.0 FOR BOND WIRE SIZE AND INSULATION REQUIREMENTS.
- 2. FOR TEST LEAD WIRE REQUIREMENTS, SEE DETAIL C/3.0 AND NOTE 1.
- 3. RUN ALL WIRES IN 2" PVC SCH40 CONDUIT FROM THE CONNECTION POINT UNTIL THEY REACH THE BOTTOM OF TEST STATION ASSEMBLY.

WASHINGTON SUBURBAN SANITARY COMMISSION APPROVED: 7-26-21

Mile Harmur

Chief Engineer

STANDARD DETAIL

VALVE TO MAIN INSULATED FLANGE JOINT (UNRESTRAINED) 3.2