



NOTES:

1. PROVIDE THIS CONNECTION ON ALL SHC'S. UNLESS OTHERWISE INDICATED ON THE DRAWINGS OR UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
2. FOR CONTINUATION, SEE DETAILS, S/6.0, S/6.1 S/6.2, S/6.3, S/6.3a, S/6.4, S/6.5 AND S/6.7.
3. VERTICAL RISER AND 1/8 BEND SHALL BE SAME DIAMETER AS HORIZONTAL SHC PIPE.
4. CONCRETE ENCASEMENT NOT REQUIRED FOR DUCTILE IRON WYE AND BEND.
5. CONCRETE ENCASEMENT SHALL BE PRECAST WITH MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI AT 28 DAYS.
 - A) JOB SITE PRECAST SHALL BE CURED AT LEAST 7 DAYS BEFORE INSTALLATION.
 - B) APPROVED MANUFACTURER'S PRECAST SHALL BE CURED AT LEAST 80% OF REQUIRED STRENGTH BEFORE DELIVERY.
6. FOR OPTION 2 INSTALLATION PROVIDE 2"x4" SHC MARKER BOARD PER SPECIFICATIONS. SOIL FROM CAP TO 12" ABOVE CAP SHALL BE HAND TAMPERED ONLY.
7. ALL HOUSE CONNECTION RENEWALS WILL BE TERMINATED IN ACCORDANCE WITH DETAIL S/5.0.

WASHINGTON
SUBURBAN
SANITARY
COMMISSION

APPROVED: 7-7-21
M. W. Harmon
Chief Engineer

STANDARD DETAIL
4-INCH AND 6-INCH SEWER
HOUSE CONNECTIONS
TERMINATING AT THE
PROPERTY LINE

S
6.8